BRUHATH BANGALORE MAHANAGARA PALIKE
DTS

Issued to Sri

TEND NO:
ITEM NO:
Orginal/Duplicate

NAME OF WORK: Improvements to drain & Construction of culverts at W type HMT qtrs in ward no 16

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	432.00	Earthwork excavation for the foundations of the buildings,water supply,sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of the pits and trenches,stacking the excavated soil clear from the excavations with lead upto 50m after breaking of clod complete a per specifications	cum	201.96	Rupees Two Hundred One and Ninety Six Paise Only
2	36.00	Providing sand cement bed with 5% cement with all leads for all materials and lift of 1.5m.machine mixed,laid in layers of 15cms .thick and well compacted for fondation,including curing cost of materials labour and HOM complete as per Specification	cum	2141.64	Rupees Two Thousand One Hundred Forty One and Sixty Four Paise Only
3	54.00	Providing and laying in position plain cement concrete of 1 mix M7.5 with OPC cement @ 180kgs, with 40mm down size granite metal coarse aggregates @0.85cum and fineaggregtes @0.57 cum m machine mixed, machine mixed concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, includig cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	3884.76	Rupees Three Thousand Eight Hundred Eighty Four and Seventy Six Paise Only
4	140.40	Providing and constructing granite/ trap/basalt size stone masonry in basement with cement mortar 1:6,edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	3223.80	Rupees Three Thousand Two Hundred Twenty Three and Eighty Paise Only
5	25.92	Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation , plinth and cills, including cos of all materials, labour, HOM machinery, curing complete as per specifications	cum	4409.64	Rupees Four Thousand Four Hundred Nine and Sixty Four Paise Only
6	234.00	Providing flush pointing to square rubble,course or uncoursed stone masonry with CM1:3,20mm deep after raking joints to depth of 20mm nicely lining,including cost of materials,labour,currong complete as per specification	cum	71.39	Rupees Seventy One and Thirty Nine Paise Only

Signature of the contractor

22/12/13
C.E (R.R.N.)

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

7	108.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar 7.50 cms thick including fixing curing etc., complete.	cum	315.36	Rupees Three Hundred Fifteen and Thirty Six Paise Only
8	108.00	Providing and removing centering, shuttering, strutting, propping etc,and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes,thickness upto200mm including cost of all materials,labour complete as per specifications	sqm	315.36	Rupees Three Hundred Fifteen and Thirty Six Paise Only
9	74.52	Providing and laying in position reinforced cement conctrete of design mix M 20 with OPC cement @ 320kgs with 20mm and down size graded granite metalcoarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum,with super plastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed,concrete laid in layersnot exceeding 15 cms thick,vibrated for all works in foundation plinth and ground floor level for roof slabs,staircase,lintles,retaining walls,return walls,walls(any thickness) including attached plasters,columns,piers,abutments,pillars,posts,struts,buttresses,string or lacing courses,parapets,coping,bed blocks,anchor blocks,plain window cills,fillets etc.including cost of all materials,labour,HOM of machinery,curing,complete as per specifications	cum	5239.08	Rupees Five Thousand Two Hundred Thirty Nine and Eight Paise Only
10	74.42	Providing T.M.T. steel reinforcemnet for R.C.C. work including straightening, cutting bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete asper design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	qtl	7323.48	Rupees Seven Thousand Three Hundred Twenty Three and Forty Eight Paise Only
11	344.00	Conveying the excavated earth slit debris and over burden earth etc.,to a lead of 10 to 15kms distance by using private vehicle thi include the cost of loading and unloading charges etc.,complete	cum	108.64	Rupees One Hundred Eight and Sixty Four Paise Only

Signature of the Contractor

"ಓಕೆ ಮಾಡಿಸಿರಿ"

20/12/13

ಮುಖ್ಯ ಅಧಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ

Executive Engineer
Rajarajeshwarinagara Division
B.B.M.P

Scanned by CamScanner